

දකුණු පළාත් සංවර්ධන සැලැස්ම - 2025

පළාත් නිශ්චිත සංවර්ධන ප්‍රදාන

පළාත් පාලන මාරග - නව වැඩ

අතුරුලිය ප්‍රාදේශීය සභාව

නිබ්බන්ධාවාද නලගස්ස කාණු පද්ධතිය සංවර්ධනය

Estimate						
Item	Description of work	Code	Unit	Qty:	Rate	Amount
1.0	<u>EXCAVATION AND EARTH WORK</u>					
1.1	Cutting side drains of Standard dimensions in unclassified soils using machine (Backhoe JCB) including , trimming and levelling bottom manually	DR-005A	m ³	39.50		
1.2	Approved soil (type I & II materials) Excavation for bases & shoulder construction including loading and pilling (loose volume) 2 ton vib. Roller	EW-003B + 013	m ³	9.25		
	Carried to Summary					
2.0	<u>CONCRETOR</u>					
2.1	Mixing & Laying Using Concrete Mixer, cement concrete 1:3:6 (37.5mm) (Volume Batching) using crushed aggregate (incl. Transport of Aggregate & pilling)	ST-041	m ³	4.70		
2.2	Mixing & Laying Using Concrete Mixer, cement concrete 1:2:4 (19mm) (Volume Batching) using crushed aggregate (incl. Transport of Aggregate & pilling)	ST-047	m ³	43.00		
	Carried to Summary					
3.0	<u>REINFORCEMENT</u>					
3.1	Reinforcement for drain & cover slab	R/F-01	Kg	3265.00		
	Carried to Summary					
4.0	<u>FORMWORK</u>					
4.1	Formwork for drain	FW-03	M ²	481.00		
	Carried to Summary					
5.0	<u>MISCELLENIOUS</u>					
5.1	Allow for testing of concrete		Nr	15.00		
	Carried to Summary					

Prepared by:-

Checked by:-